

ALS Group USA, Corp.

10450 Stancliff Rd. Suite 210 Houston, Texas 77099

Certified Product Listing

For:

Drinking Water System Components - Health Effects

Company:

Zurn Water, LLC - Wilkins 1747 Commerce Way Paso Robles, CA 93446, United States

Plant Location:

Paso Robles, CA, United States

Standards:

NSF/ANSI/CAN 61 - 2022 NSF/ANSI 372 - 2022

Certificate:

Issued Date: 02/06/2018

Material/Product:

Dual Check Valve (700XL & 705)

Contact Temperature:

23 ± 2°C

Models:

[A][B]X[A][B]-700XL (Size 1/4" â€" 1") [A][C]X[A][C]-705 (Size 3/4" â€" 1")

[A] indicates end connection diameter

14 = 1/4"

38 = 3/8"

12 = 1/2"

34 = 3/4"

1 = 1"

[B] indicates end connection type 700XL F or UF = Female NPT Connection

M or UM = Male NPT Connection MM or UMM = Male Meter Connection

FM or UFM = Female Meter Connection

FC or UFC = Female Copper Connection

[C] indicates end connection type 705

F or UF = Female NPT

UFM = Female Meter Connection

UM = Male NPT

UFC = Female Copper

The â€~U' designates a union connection between the end connection and the meter body



