



ALS Group USA, Corp.

10450 Stancliff Rd. Suite 210 Houston, Texas 77099

Certified Product Listing

For:

Drinking Water System Components – Health Effects

Company:

Alchatek, LLC
4508 Bibb Blvd
Suite B-5
Tucker, GA 30084, United States

Plant Location:

Tucker, GA, United States

Standards:

NSF/ANSI/CAN 61 - 2022
NSF/ANSI 372 - 2022

Certificate:

Issued Date: 02/28/2024

Material/Product:

Spetec AG200 - Acrylic gel used for sealing leaks and stablizing Soil

Contact Temperature:

23 ± 2°C

Models:

Spetec AG 200



Product certified to NSF/ANSI/CAN 372 conforms to the requirements for "Lead Free" plumbing products as defined by California, Vermont, Maryland and Louisiana state laws and by section 1417 of the US SDWA.



Material Characteristics:

Minimum tank size (gallons): 5000

Maximum tank surface area/volume ratio (sq in/L): 3.3

Is additional coating required (e.g. top coat, primer, intermediate coat)? (Y/N): No

Total cure time and temperature: 48 hrs at $23 \pm 2^\circ\text{C}$

Final cure time: 7 days at $23 \pm 2^\circ\text{C}$

Mix ratio: 20:1.1:1:18

Is this paint/coating system intended to be applied to a pipe? (Y/N): No

ALS